



**Key**

- Adjust and relay existing slabbed footway and tactile crossing
- Lift/adjust existing dropped kerbs to level of plateau
- Existing belisha beacon to remain insitu
- New gully and connection at bottom of plateau to prevent ponding

NB - Plateau to be constructed to NCC standard details ESD 4/44 and ESD 4/45. Flat top section of plateau to be minimum 8.0m due to bus route, ramps to be 1.1m

Rev Status	Description	Drawn	Chkd	Auth	Date
Project	High Street, Mansfield Woodhouse				
Status	Project No. BD/FR/01/MWH				
Title	Zebra on raised plateau construction details				
Scale	Drawn BD			Date	
1:250 @ A3	Chkd DB			Date	
	Auth DB	Traced			
Drawing No.	BD/FR/01/MWH/03.1				Rev

in partnership with

[www.viaem.co.uk](http://www.viaem.co.uk) | Tel 0115 804 2100  
 Bilsthorpe Depot, Bilsthorpe  
 Business Park, Bilsthorpe,  
 Nottinghamshire NG22 8ST