NORTH

Crossroads Bungalow

BECKL

TE

MARK LANE

1

3

1

9

10

11

12

13

14

15

16

TUXFORD ROAD

15m

BUS STOP

BUS STOP

Proposed New Bus Stop Pole Location

Install new 15m No Waiting At Any Time Double Yellow Lines

Proposed New 19m Bus Clearway location (No Stopping At Any Time Except Buses)

Existing Bus Clearway to be removed/relocated

Existing Bus Stop Pole to be Relocated ref BA0554

© Crown copyright and database rights 2025 Ordnance Survey 100019713.

KEY

- Proposed New Bus Stop Pole Location
- Proposed New 19m Bus Clearway Location (No Stopping At Any Time Except Buses)
- Proposed Raised Kerbs
- Proposed Transition Kerbs
- Proposed New Double Yellow Lines
- Existing Bus Clearway to be relocated/removed
- Existing Bus stop pole to be removed/relocated ref BA0554
- Existing Bus Clearway to be retained
- Existing Bus Stop Pole ref BA0523 to be retained

Rev.	Description	Drawn	Ch'kd	Auth	Date

Project

Tuxford Rd, East Markham

Status	Project No.
STG 2	TP2350516 - NNS17

Drawing Title

Proposed Bus Stop Imrovements

Scale	Drawn	Date
NTS	JC	JUL' 25
	Ch'kd: MW	Date: JUL' 25
	Auth: MN	Traced

Drawing No.	Rev.
H/JC/5020/01/A	A

via

in partnership with Nottinghamshire County Council

www.viaem.co.uk Tel 0115 804 2100

Bilsthorpe Depot, Bilsthorpe Business Park, Bilsthorpe, Nottinghamshire, NG22 8ST

© Via East Midlands Limited,Registered in England no.09903246

A3

Jan 27,2026 - 1:21pm C:\Users\TafadzwaSoko\DCACDocs\ViaEMIT\P2350516 Note BSIP A6 – Operator Pinch Point Package – Notts Non School\Project Files\10 OPP\NNS17 & NNS7 - Tuxford Road, Mark Lane, East Markham\B Design Phase\B03 Drawing\NNS17 Tuxford Rd, Newerd works plan.dwg